

LAND APPLICATION SITE

BOBBY MCDANIEL

GRBXM 1 - 10

GREENE COUNTY

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION
FORM D: MUNICIPAL EFFLUENT AND BIOSOLIDS**

PART D-VI: LAND APPLICATION AGREEMENT - BIOSOLIDS AND INDUSTRIAL RESIDUALS

A. This land application agreement is made on 4-30-18 between Bobby McDaniel referred to here as "Landowner", and Recvc Systems, Inc. referred to here as the "Permittee". This agreement remains in effect until it is terminated in writing by either party or, with respect to those parcels that are retained by the Landowner in the event of a sale of one or more parcels, until ownership of all parcels changes. If ownership of individual parcels identified in this agreement changes, those parcels for which ownership has changed will no longer be authorized to receive biosolids or industrial residuals under this agreement.

Landowner:

The Landowner is the owner of record of the real property located in Huckersville, Virginia, which includes the agricultural, silvicultural or reclamation sites identified below in Table 1 and identified on the tax map(s) attached as Exhibit A.

Table 1.: Parcels authorized to receive biosolids, water treatment residuals or other industrial sludges			
Tax Parcel ID	Tax Parcel ID	Tax Parcel ID	Tax Parcel ID
38-A-122			
38-A-124			
38-A-123			
51-A-3			

☐ Additional parcels containing Land Application Sites are identified on Supplement A (check if applicable)

Check one:

- ☐ The Landowner is the sole owner of the properties identified herein.
☒ The Landowner is one of multiple owners of the properties identified herein.

In the event that the Landowner sells or transfers all or part of the property to which biosolids have been applied within 38 months of the latest date of biosolids application, the Landowner shall:

1. Notify the purchaser or transferee of the applicable public access and crop management restrictions no later than the date of the property transfer; and
2. Notify the Permittee of the sale within two weeks following property transfer.

The Landowner has no other agreements for land application on the fields identified herein. The Landowner will notify the Permittee immediately if conditions change such that the fields are no longer available to the Permittee for application or any part of this agreement becomes invalid or the information herein contained becomes incorrect.

The Landowner hereby grants permission to the Permittee to land apply residuals as specified below, on the agricultural sites identified above and in Exhibit A. The Landowner also grants permission for DEQ staff to conduct inspections on the land identified above, before, during or after land application of permitted residuals for the purpose of determining compliance with regulatory requirements applicable to such application.

<u>Class B biosolids</u>	<u>Water treatment residuals</u>	<u>Food processing waste</u>	<u>Other industrial sludges</u>
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

Bobby McDaniel
Landowner - Printed Name, Title

Bobby McDaniel
Signature

145 McDaniel Lane Huckersville
Mailing Address & Phone Number Va.
434-985-7591 22968

Permittee:

Recvc Systems, Inc., the Permittee, agrees to apply biosolids and/or industrial residuals on the Landowner's land in the manner authorized by the VPA Permit Regulation and in amounts not to exceed the rates identified in the nutrient management plan prepared for each land application field by a person certified in accordance with §10.1-104.2 of the Code of Virginia.

The Permittee agrees to notify the Landowner or the Landowner's designee of the proposed schedule for land application and specifically prior to any particular application to the Landowner's land. Notice shall include the source of residuals to be applied.

☐ I reviewed the document(s) assigning signatory authority to the person signing for landowner above. I will make a copy of this document(s) available to DEQ for review upon request. (Do not check this box if the landowner signs this agreement)

[Signature]
Permittee - Authorized Representative
Printed Name

[Signature]
Signature

PO Box 562 Remington, Virginia 22734
Mailing Address

VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION: PART D-VI LAND APPLICATION AGREEMENT

Permittee: Recvc Systems, Inc

County or City: Greene

Landowner: Bobby McDaniel

Landowner Site Management Requirements:

I, the Landowner, I have received a DEQ Biosolids Fact Sheet that includes information regarding regulations governing the land application of biosolids, the components of biosolids and proper handling and land application of biosolids.

I have also been expressly advised by the Permittee that the site management requirements and site access restrictions identified below must be complied with after biosolids have been applied on my property in order to protect public health, and that I am responsible for the implementation of these practices.

I agree to implement the following site management practices at each site under my ownership following the land application of biosolids at the site:

1. Notification Signs: I will not remove any signs posted by the Permittee for the purpose of identifying my field as a biosolids land application site, unless requested by the Permittee, until at least 30 days after land application at that site is completed.
2. Public Access
 - a. Public access to land with a high potential for public exposure shall be restricted for at least one year following any application of biosolids.
 - b. Public access to land with a low potential for public exposure shall be restricted for at least 30 days following any application of biosolids. No biosolids amended soil shall be excavated or removed from the site during this same period of time unless adequate provisions are made to prevent public exposure to soil, dusts or aerosols;
 - c. Turf grown on land where biosolids are applied shall not be harvested for one year after application of biosolids when the harvested turf is placed on either land with a high potential for public exposure or a lawn, unless otherwise specified by DEQ.
3. Crop Restrictions:
 - a. Food crops with harvested parts that touch the biosolids/soil mixture and are totally above the land surface shall not be harvested for 14 months after the application of biosolids.
 - b. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after the application of biosolids when the biosolids remain on the land surface for a time period of four (4) or more months prior to incorporation into the soil,
 - c. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months when the biosolids remain on the land surface for a time period of less than four (4) months prior to incorporation.
 - d. Other food crops and fiber crops shall not be harvested for 30 days after the application of biosolids;
 - e. Feed crops shall not be harvested for 30 days after the application of biosolids (60 days if fed to lactating dairy animals).
4. Livestock Access Restrictions:

Following biosolids application to pasture or hayland sites:

 - a. Meat producing livestock shall not be grazed for 30 days,
 - b. Lactating dairy animals shall not be grazed for a minimum of 60 days.
 - c. Other animals shall be restricted from grazing for 30 days;
5. Supplemental commercial fertilizer or manure applications will be coordinated with the biosolids and industrial residuals applications such that the total crop needs for nutrients are not exceeded as identified in the nutrient management plan developed by a person certified in accordance with §10.1-104.2 of the Code of Virginia;
6. Tobacco, because it has been shown to accumulate cadmium, should not be grown on the Landowner's land for three years following the application of biosolids or industrial residuals which bear cadmium equal to or exceeding 0.45 pounds/acre (0.5 kilograms/hectare).

Bobby McDaniel
Landowner's Signature

4-30-18
Date

Bobby McDaniel
Farm Operator Signature

145 McDaniel Lane Ruckersville Va
Mailing Address & Phone Number

434-985-7591

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION
FORM D: MUNICIPAL EFFLUENT AND BIOSOLIDS**

PART D-VI: LAND APPLICATION AGREEMENT - BIOSOLIDS AND INDUSTRIAL RESIDUALS

A. This land application agreement is made on 5-14-18 between JoAnn McDaniel referred to here as "Landowner", and Recyc Systems, Inc. referred to here as the "Permittee". This agreement remains in effect until it is terminated in writing by either party or, with respect to those parcels that are retained by the Landowner in the event of a sale of one or more parcels, until ownership of all parcels changes. If ownership of individual parcels identified in this agreement changes, those parcels for which ownership has changed will no longer be authorized to receive biosolids or industrial residuals under this agreement.

Landowner:

The Landowner is the owner of record of the real property located in Greene, Virginia, which includes the agricultural, silvicultural or reclamation sites identified below in Table 1 and identified on the tax map(s) attached as Exhibit A.

Table 1.: Parcels authorized to receive biosolids, water treatment residuals or other industrial sludges			
Tax Parcel ID	Tax Parcel ID	Tax Parcel ID	Tax Parcel ID
38-A-122			
38-A-124			
38-A-123			
51-A-3			

☐ Additional parcels containing Land Application Sites are identified on Supplement A (check if applicable)

Check one:

- ☐ The Landowner is the sole owner of the properties identified herein.
☒ The Landowner is one of multiple owners of the properties identified herein.

In the event that the Landowner sells or transfers all or part of the property to which biosolids have been applied within 38 months of the latest date of biosolids application, the Landowner shall:

1. Notify the purchaser or transferee of the applicable public access and crop management restrictions no later than the date of the property transfer; and
2. Notify the Permittee of the sale within two weeks following property transfer.

The Landowner has no other agreements for land application on the fields identified herein. The Landowner will notify the Permittee immediately if conditions change such that the fields are no longer available to the Permittee for application or any part of this agreement becomes invalid or the information herein contained becomes incorrect.

The Landowner hereby grants permission to the Permittee to land apply residuals as specified below, on the agricultural sites identified above and in Exhibit A. The Landowner also grants permission for DEQ staff to conduct inspections on the land identified above, before, during or after land application of permitted residuals for the purpose of determining compliance with regulatory requirements applicable to such application.

<u>Class B biosolids</u>	<u>Water treatment residuals</u>	<u>Food processing waste</u>	<u>Other industrial sludges</u>
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

<u>JoAnn C McDaniel</u>	<u>145 McDaniel Lane</u>
Landowner - Printed Name, Title	Mailing Address & Phone Number
	<u>22968</u>
	<u>434-985-7591</u>

Permittee:

Recyc Systems, Inc., the Permittee, agrees to apply biosolids and/or industrial residuals on the Landowner's land in the manner authorized by the VPA Permit Regulation and in amounts not to exceed the rates identified in the nutrient management plan prepared for each land application field by a person certified in accordance with §10.1-104.2 of the Code of Virginia.

The Permittee agrees to notify the Landowner or the Landowner's designee of the proposed schedule for land application and specifically prior to any particular application to the Landowner's land. Notice shall include the source of residuals to be applied.

☐ I reviewed the document(s) assigning signatory authority to the person signing for landowner above. I will make a copy of this document(s) available to DEQ for review upon request. (Do not check this box if the landowner signs this agreement)

<u>[Signature]</u>	<u>[Signature]</u>	<u>PO Box 562 Remington, Virginia 22734</u>
Permittee - Authorized Representative	Signature	Mailing Address
Printed Name		

VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION: PART D-VI LAND APPLICATION AGREEMENT

Permittee: Racyc Systems, Inc

County or City: Greene

Landowner: JoAnn McDaniel

Landowner Site Management Requirements:

I, the Landowner, I have received a DEQ Biosolids Fact Sheet that includes information regarding regulations governing the land application of biosolids, the components of biosolids and proper handling and land application of biosolids.


I have also been expressly advised by the Permittee that the site management requirements and site access restrictions identified below must be complied with after biosolids have been applied on my property in order to protect public health, and that I am responsible for the implementation of these practices.

I agree to implement the following site management practices at each site under my ownership following the land application of biosolids at the site:

1. Notification Signs: I will not remove any signs posted by the Permittee for the purpose of identifying my field as a biosolids land application site, unless requested by the Permittee, until at least 30 days after land application at that site is completed.
2. Public Access
 - a. Public access to land with a high potential for public exposure shall be restricted for at least one year following any application of biosolids.
 - b. Public access to land with a low potential for public exposure shall be restricted for at least 30 days following any application of biosolids. No biosolids amended soil shall be excavated or removed from the site during this same period of time unless adequate provisions are made to prevent public exposure to soil, dusts or aerosols;
 - c. Turf grown on land where biosolids are applied shall not be harvested for one year after application of biosolids when the harvested turf is placed on either land with a high potential for public exposure or a lawn, unless otherwise specified by DEQ.
3. Crop Restrictions:
 - a. Food crops with harvested parts that touch the biosolids/soil mixture and are totally above the land surface shall not be harvested for 14 months after the application of biosolids.
 - b. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after the application of biosolids when the biosolids remain on the land surface for a time period of four (4) or more months prior to incorporation into the soil,
 - c. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months when the biosolids remain on the land surface for a time period of less than four (4) months prior to incorporation.
 - d. Other food crops and fiber crops shall not be harvested for 30 days after the application of biosolids;
 - e. Feed crops shall not be harvested for 30 days after the application of biosolids (60 days if fed to lactating dairy animals).
4. Livestock Access Restrictions:

Following biosolids application to pasture or hayland sites:

 - a. Meat producing livestock shall not be grazed for 30 days,
 - b. Lactating dairy animals shall not be grazed for a minimum of 60 days.
 - c. Other animals shall be restricted from grazing for 30 days;
5. Supplemental commercial fertilizer or manure applications will be coordinated with the biosolids and industrial residuals applications such that the total crop needs for nutrients are not exceeded as identified in the nutrient management plan developed by a person certified in accordance with §10.1-104.2 of the Code of Virginia;
6. Tobacco, because it has been shown to accumulate cadmium, should not be grown on the Landowner's land for three years following the application of biosolids or industrial residuals which bear cadmium equal to or exceeding 0.45 pounds/acre (0.5 kilograms/hectare).


Landowner's Signature

5-14-18
Date

Farm Operator Signature

Mailing Address & Phone Number

FARM DATA SHEET

SITE NAME:	Bobby McDaniel	COUNTY:	Greene
OWNER:	Bobby F. and Joann C. McDaniel	OPERATOR:	Bobby McDaniel
OWNER'S ADDRESS:	145 McDaniel Lane Ruckersville, VA 22968	OPERATOR'S ADDRESS:	145 McDaniel Lane Ruckersville, VA 22968
OWNER'S TELEPHONE:	434-985-7591	OPERATOR'S TELEPHONE:	434-985-7591
GENERAL FARM TYPE:	Pasture/ Hay/ Row Crops	CELL PHONE:	-
# CATTLE:	70	EMAIL:	-
LAGOON or SLURRY:	None	LATITUDE:	38.271
TOPO QUAD:	Stanardsville	LONGITUDE:	78.400
COMMENTS:	METHOD OF DETERMINATION: Online Maps		

BBK
5-21-18

Bobby McDaniel

Greene Co.

Old Field 10B is New Field 3.

Part of New Field 3 is Old Field 9.

RECYC SYSTEMS, INC

FIELD DATA SHEET

Field Identification	DEQ Control ID	Gross Acres	Environmentally Sensitive Soils				Hydro Map	Tax Map #	FSA Tract #
			Water Table	Bed Rock/ Shallow	Surf/Leach	Freq Flood			
GRBXM 1	51079-00030-0000	13.0	Hb Oct.-May	AsD	AsD, Hb	Hb Oct.-May	RA 26	38-A-122	T 462 F 2, 5
GRBXM 2	51079-00031-0000	18.4	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	38-A-122	T 462 F 6
GRBXM 3	51079-00038-0000	18.2	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	38-A-122 51-A-3	T 462 F 8
GRBXM 4	51079-00032-0000	10.7	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	38-A-122	T 462 F 9
GRBXM 5	51079-00033-0000	16.4	Hb Oct.-May	AsD	AsD, Hb	Hb Oct.-May	RA 26	51-A-3	T 464 F 11, 13
GRBXM 6	51079-00034-0000	4.7	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	38-A-122	T 462 F 1
GRBXM 7	51079-00035-0000	11.4	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	38-A-122 51-A-3	T 462 F 8
GRBXM 8	51079-00036-0000	20.9	Hb Oct.-May	-	Hb	Hb Oct.-May	RA 26	51-A-3	T 464 F 14, 15
GRBXM 9	51079-00037-0000	4.7	Hb Oct.-May	AsC, AsD	AsC, AsD, Hb	Hb Oct.-May	RA 26	51-A-3	T 462 F 16
GRBXM 10	51079-00038-0000	17.8	CgB Dec.-May Hb Oct.-May	AsC	AsC, Hb	Hb Oct.-May	RA 26	38-A-122 51-A-3	T 462 F 8
TOTAL ACRES IN SITE		136.2							

8-24-2020

Landowner Coordination Form

Signature not required on this page

[illegible]

Report Number: 17-254-0556

Account Number: 70594



"Every acre...Every year."™

7621 Whitepine Road, Richmond, VA 23237

Main 804-743-9401 • Fax 804-271-6446

www.waypointanalytical.com

Send To: Recyc Systems Inc
Susan Trumbo
8455 Whiteshop Road
Culpeper VA 22701

Grower: Bobby McDaniel

SOIL ANALYSIS REPORT

Analytical Method(s): SMP Buffer pH Mehlich 3 Loss On Ignition Water pH

Date Received: 09/11/2017

Date Of Analysis: 09/12/2017

Date Of Report: 09/12/2017

Sample ID Field ID	Lab Number	OM	W/V	ENR	Phosphorus				Potassium	Magnesium	Calcium	Sodium	pH		Acidity	C.E.C
		% Rate	Soil Class	lbs/A	M3 ppm Rate	ppm Rate	ppm Rate	K ppm Rate	Mg ppm Rate	Ca ppm Rate	Na ppm Rate	Soil pH	Buffer Index	H meq/100g	meq/100g	
4	23704	5.0 H		136	81 H			62 L	80 L	1595 H		6.5	6.86	0.7	9.5	
5	23705	8.4 VH		150	46 M			295 VH	160 M	1097 M		5.9	6.77	1.6	9.2	
8	23706	6.8 H		150	58 H			365 VH	207 H	1416 M		6.1	6.78	1.5	11.2	
10A	23707	5.0 H		139	58 H			70 L	110 M	1042 M		5.8	6.78	1.5	7.8	
3	23709	5.7 H		149	95 H			117 M	121 L	1636 H		6.5	6.85	0.8	10.3	

Sample ID Field ID	Percent Base Saturation					Nitrate	Sulfur	Zinc	Manganese	Iron	Copper	Boron	Soluble Salts		
	K %	Mg %	Ca %	Na %	H %	NO ₃ N ppm Rate	S ppm Rate	Zn ppm Rate	Mn ppm Rate	Fe ppm Rate	Cu ppm Rate	B ppm Rate	SS ms/cm Rate		
4	1.7	7.0	83.9		7.4			5.6 H	65 VH						
5	8.2	14.5	59.6		17.4			4.5 H	71 VH						
8	8.4	15.4	63.2		13.4			5.5 H	52 VH						
10A	2.3	11.8	66.8		19.2			5.5 H	35 H						
3	2.9	9.8	79.4		7.8			6.1 H	63 VH						

Values on this report represent the plant available nutrients in the soil. Rating after each value: VL (Very Low), L (Low), M (Medium), H (High), VH (Very High). ENR - Estimated Nitrogen Release. C.E.C. - Cation Exchange Capacity.

Explanation of symbols: % (percent), ppm (parts per million), lbs/A (pounds per acre), ms/cm (milli-mhos per centimeter), meq/100g (milli-equivalent per 100 grams). Conversions: ppm x 2 = lbs/A, Soluble Salts ms/cm x 640 = ppm.

This report applies to sample(s) tested. Samples are retained a maximum of thirty days after testing.

Analysis prepared by: Waypoint Analytical Virginia, Inc.

by: *Paucic McGeary*

Paucic McGeary

Report Number: 17-254-0556

Account Number: 70594

*"Every acre...Every year."™*

7621 Whitepine Road, Richmond, VA 23237

Main 804-743-9401 ° Fax 804-271-6446

www.waypointanalytical.com

Send To: Recyc Systems Inc
Susan Trumbo
8455 Whiteshop Road
Culpeper VA 22701

Grower: Bobby McDaniel

Date Received: 09/11/2017

Date Of Report: 09/12/2017

SOIL FERTILITY RECOMMENDATIONS

Sample ID Field ID	Intended Crop	Yield Goal	Lime Tons/A	Nitrogen N lb/A	Phosphate P ₂ O ₅ lb/A	Potash K ₂ O lb/A	Magnesium Mg lb/A	Sulfur S lb/A	Zinc Zn lb/A	Manganese Mn lb/A	Iron Fe lb/A	Copper Cu lb/A	Boron B lb/A
4	Adjust pH to 6.8	0	1.0				0			0			
5	Adjust pH to 6.8	0	1.8				0			0			
8	Adjust pH to 6.8	0	1.5				0			0			
10A	Adjust pH to 6.8	0	1.8				0			0			
3	Adjust pH to 6.8	0	1.0				0			0			

Comments:**Sample(s) : 10A Crop: Adjust pH to 6.8**

Apply dolomitic lime to raise pH and improve the magnesium level.

"The recommendations are based on research data and experience, but NO GUARANTEE or WARRANTY expressed or implied, concerning crop performance is made."

Our reports and letters are for the exclusive and confidential use of our clients,, and may not be reproduced in whole or part, nor may any reference be made to the work, the results, or the company in any advertising, news release, or other public announcements without obtaining our prior written authorization. Copy right 1977.

Pauric McGroary

Report Number: 15-232-0523

Account Number: 70594



7621 Whitepine Road, Richmond, VA 23237
Main 804-743-9401 ° Fax 804-271-6446
www.waypointanalytical.com

Send To: RECYC SYSTEMS INC
SUSAN TRUMBO
8455 WHITESHOP RD
CULPEPER VA 22701

"Every acre...Every year."™

Submitted By: BB

Grower: BOBBY MCDANIEL
GREENE
GRBXM

SOIL ANALYSIS REPORT

Analytical Method(s):
Mehlich 3

Date Received: 08/20/2015

Date Of Analysis: 08/21/2015

Date Of Report: 08/21/2015

Sample ID Field ID	Lab Number	Organic Matter			Phosphorus			Potassium		Magnesium		Calcium		Sodium		pH		Acidity	C.E.C
		%	Rate	ENR lbs/A	Mehlich 3 ppm	Rate	Reserve ppm	K ppm	Rate	Mg ppm	Rate	Ca ppm	Rate	Na ppm	Rate	Soil pH	Buffer Index	H meq/100g	meq/100g
1	03794	3.8	M	118	35	M		92	M	79	M	498	L			5.1	6.73	2.0	5.4
2	03795	4.8	M	136	42	M		276	VH	179	H	699	L			5.7	6.78	1.5	7.2
7	03796	5.2	H	139	20	L		72	L	129	M	1870	VH			7.2		0.0	10.6
8	03797	4.6	M	130	40	M		289	VH	142	M	976	M			5.9	6.79	1.4	8.2
10A	03798	4.7	M	132	47	M		70	L	131	M	1132	M			6.0	6.80	1.3	8.2

Sample ID Field ID	Percent Base Saturation					Nitrate		Sulfur		Zinc		Manganese		Iron		Copper		Boron		Soluble Salts		Chloride		Aluminum
	K %	Mg %	Ca %	Na %	H %	NO ₃ N ppm	Rate	S ppm	Rate	Zn ppm	Rate	Mn ppm	Rate	Fe ppm	Rate	Cu ppm	Rate	B ppm	Rate	SS ms/cm	Rate	Cl ppm	Rate	Al ppm
1	4.4	12.2	46.1		37.7					3.2	M	37	H											
2	9.8	20.7	48.5		21.1					3.9	H	22	H											
7	1.7	10.1	88.2		0.0					3.7	H	56	VH											
8	9.0	14.4	59.5		17.2					3.1	M	73	VH											
10A	2.2	13.3	69.0		15.4					4.7	H	63	VH											

Values on this report represent the plant available nutrients in the soil. Rating after each value: VL (Very Low), L (Low), M (Medium), H (High), VH (Very High). ENR - Estimated Nitrogen Release. C.E.C. - Cation Exchange Capacity.

Explanation of symbols: % (percent), ppm (parts per million), lbs/A (pounds per acre), ms/cm (milli-mhos per centimeter), meq/100g (milli-equivalent per 100 grams). Conversions: ppm x 2 = lbs/A, Soluble Salts ms/cm x 640 = ppm.

This report applies to sample(s) tested. Samples are retained a maximum of thirty days after testing.

Analysis prepared by: Waypoint Analytical Virginia, Inc.

by: *Paucic McGeary*

Paucic McGeary

Report Number: 15-232-0523

Account Number: 70594



7621 Whitepine Road, Richmond, VA 23237

Main 804-743-9401 • Fax 804-271-6446

www.waypointanalytical.com

Send To: RECYC SYSTEMS INC
SUSAN TRUMBO
8455 WHITESHOP RD
CULPEPER VA 22701

"Every acre...Every year."™

Submitted By: BB

Grower: BOBBY MCDANIEL
GREENE
GRBXM

Date Received: 08/20/2015

Date Of Report: 08/21/2015

SOIL FERTILITY RECOMMENDATIONS

Sample ID Field ID	Intended Crop	Yield Goal	Lime Tons/A	Nitrogen N lb/A	Phosphate P ₂ O ₅ lb/A	Potash K ₂ O lb/A	Magnesium Mg lb/A	Sulfur S lb/A	Zinc Zn lb/A	Manganese Mn lb/A	Iron Fe lb/A	Copper Cu lb/A	Boron B lb/A
1	Adjust pH to 6.8	0	2.3				1			0			
2	Adjust pH to 6.8	0	1.8				0			0			
7	Adjust pH to 6.8	0	0.0				0			0			
8	Adjust pH to 6.8	0	1.8				0			0			
10A	Adjust pH to 6.8	0	1.5				0			0			

Comments:

"The recommendations are based on research data and experience, but NO GUARANTEE or WARRANTY expressed or implied, concerning crop performance is made."

Our reports and letters are for the exclusive and confidential use of our clients, and may not be reproduced in whole or part, nor may any reference be made to the work, the results, or the company in any advertising, news release, or other public announcements without obtaining our prior written authorization. Copy right 1977.

Paucic McGroary

THE PLANNER IS NOT STATE CERTIFIED

Nutrient Management Plan Balance Sheet
(Spring, 2018-Summer, 2020)
Bobby McDaniel
Planner: John Doe

Tract: 462

Location: Greene

(N = N based, 1P = P based, 1.5P = P based at 1.5 removal, 0P = No P allowed)

Field CFSA No. /Name	Size (ac) Total/ Used	Yr.	Crop	Needs N-P-K (lbs/ac)	Leg /Man Resid	Manure/Biosld Rate & Type (season)	IT (d)	Man/Bios N-P-K (lbs/ac)	Net = Needs - applied N-P-K (lbs/ac)	Sum P rem cred	Commercial N-P-K (lbs/ac)	Notes	
2, 5/GRBXM 1(N)	14/14	2018	Grass Pasture	50-80-80	0/0				50-80-80	N/A			
6/GRBXM 2(N)	19/19	2018	Grass Pasture	50-30-0	0/0				50-30-0	N/A			
8/GRBXM 3(N)	20/20	2018	Fescue grass hay mt.	70-40-85	0/0				70-40-85	N/A			
9/GRBXM 4(N)	12/12	2018	Wheat (grain)	100-30-80	0/0				100-30-80	N/A			
1/GRBXM 6(N)	4/4	2018	Wheat (grain)	100-30-60	0/0				100-30-60	N/A			
8/GRBXM 7(N)	14/14	2018	Barley(silage)	100-80-60	0/0				100-80-60	N/A			
			Soybeans (DC)	0-80-60	0/0				0-160-120	N/A			
16/GRBXM 9(N)	5/5	2018	Wheat (grain)	100-60-60	0/0				100-60-60	N/A			
8/GRBXM 10(N)	20/20	2018	Orchardgrass hay mt.	90-60-185	0/0				90-60-185	N/A			

Commercial Application Methods:

br - Broadcast ba - Banded sd - Sidedress

Notes:

Tract: 464

Location: Greene

(N = N based, 1P = P based, 1.5P = P based at 1.5 removal, 0P = No P allowed)

Field CFSA No. /Name	Size (ac) Total/ Used	Yr.	Crop	Needs N-P-K (lbs/ac)	Leg /Man Resid	Manure/Biosld Rate & Type (season)	IT (d)	Man/Bios N-P-K (lbs/ac)	Net = Needs - appld N-P-K (lbs/ac)	Sum P rem cred	Commercial N-P-K (lbs/ac)	Notes	
11, 13/GRBXM 5(N)	18/18	2018	Grass Pasture	50-30-0	0/0				50-30-0	N/A			
14, 15/GRBXM 8(N)	17/17	2018	Grass Pasture	50-0-0	0/0				50-0-0	N/A			

Commercial Application Methods:

br - Broadcast ba - Banded sd - Sidedress

Notes:

Soil Test Summary

Tract	Field	Acre	Date	P2O5	K2O	Lab	Soil pH	Lime Date	rec. lime tons/Ac
462	GRBXM 1	14	2015-Su	M (35 P ppm)	M (92 K ppm)	A&L MIII	5.1		
462	GRBXM 2	19	2015-Su	M+ (42 P ppm)	VH (276 K ppm)	A&L MIII	5.7		
462	GRBXM 3	20	2017-Fa	H (95 P ppm)	M+ (117 K ppm)	A&L MIII	6.5		
462	GRBXM 4	12	2017-Fa	H (81 P ppm)	M- (62 K ppm)	A&L MIII	6.5		
462	GRBXM 6	4	2014-Fa	H (69 P ppm)	M (76 K ppm)	A&L MIII	5.7		
462	GRBXM 7	14	2015-Su	L+ (20 P ppm)	M (72 K ppm)	A&L MIII	7.2		
462	GRBXM 9	5	[No Test]						
462	GRBXM 10	20	2017-Fa	H- (58 P ppm)	M- (70 K ppm)	A&L MIII	5.8		
464	GRBXM 5	18	2017-Fa	M+ (46 P ppm)	VH (295 K ppm)	A&L MIII	5.9		
464	GRBXM 8	17	2017-Fa	H- (58 P ppm)	VH (365 K ppm)	A&L MIII	6.1		

Field Productivities for Major Crops

Tract Name	Tract/ Field	Field Name	Acres	Predominant Soil Series	Corn	Small Grain	Alfalfa	Grass Hay	Environmental Warnings
462	462/2, 5	GRBXM 1	14	Elioak	IVa	III	III	III	
	462/6	GRBXM 2*	19	Elioak	IVb	III	III	III	Poor Drainage, High Slope
	462/8	GRBXM 3	20	Meadowville	IVa	III	III	III	
	462/9	GRBXM 4	12	Meadowville	IIIa	II	III	II	
	462/1	GRBXM 6*	4	Hatboro	IVb	III	Not Suited	IV	Poor Drainage
	462/8	GRBXM 7*	14	Hatboro	IVa	II	III	III	Poor Drainage
	462/16	GRBXM 9*	5	Hatboro	IVb	III	Not Suited	IV	High Leaching, Poor Drain
	462/8	GRBXM 10	20	Meadowville	IVa	III	III	III	
	464/11, 13	GRBXM 5*	18	Hatboro	IVb	III	Not Suited	IV	High Leaching, Poor Drain
	464/14, 15	GRBXM 8*	17	Hatboro	IVb	III	III	III	Poor Drainage

* Do not apply manure or biosolids more than 30 days prior to planting. Apply commercial fertilizer nitrogen to row crops in split spring applications.

Yield Range

Field Productivity Group	Corn Grain Bu/Acre	Barley/Intensive Wheat Bu/Acre	Std. Wheat Bu/Acre	Alfalfa Tons/Acre	Grass/Hay Tons/Acre
I	>170	>80	>64	>6	>4.0
II	150-170	70-80	56-64	4-6	3.5-4.0
III	130-150	60-70	48-56	<4	3.0-3.5
IV	100-130	50-60	40-48	NA	<3.0
V	<100	<50	<40	NA	NA

Farm Summary Report

Plan: **New Plan** **Spring, 2018 - Summer, 2020**

Farm Name: **Bobby McDaniel**

Location: Greene

Specialist: John Doe

N-based Acres: 144.0

P-based Acres: 0.0

Tract Name: **462**

FSA Number: 462

Location: Greene

Field Name: **GRBXM 1**

Total Acres: 14.20 Usable Acres: 14.20

FSA Number: 2, 5

Tract: 462

Location: Greene

Slope Class: C Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Su-2015	5.1	M(35 P ppm)	M(92 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
---------	--------	-------------

9	AsD	Ashe
46	EnC3	Elioak
6	Hb	Hatboro
40	MvB	Meadowville

Field Warnings:

Field Name: GRBXM 2

Total Acres: 19.00 Usable Acres: 19.00

FSA Number: 6

Tract: 462

Location: Greene

Slope Class: C Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Su-2015	5.7	M+(42 P ppm)	VH(276 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
2	EIB	Elioak
38	EnC3	Elioak
19	EnD3	Elioak
18	Hb	Hatboro
22	MvB	Meadowville

Field Warnings:

Environmentally Sensitive Soils due to:

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

Soils with percent slope in excess of 15%

Field Name: GRBXM 3

Total Acres: 20.30 Usable Acres: 20.30

FSA Number: 8

Tract: 462

Location: Greene

Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2017	6.5	H(95 P ppm)	M+(117 K ppm)	A&L Mill	

Soils:

PERCENT	SYMBOL	SOIL SERIES
10	DkB3	Dyke
18	DkC3	Dyke
28	EnC3	Elioak
13	Hb	Hatboro
31	MvB	Meadowville

Field Warnings:

Field Name: GRBXM 4

Total Acres: 11.60 Usable Acres: 11.60
FSA Number: 9
Tract: 462
Location: Greene
Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft
Distance to stream: 0 ft

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2017	6.5	H(81 P ppm)	M-(62 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
22	EnC3	Elioak
12	Hb	Hatboro
66	MvB	Meadowville

Field Warnings:

Field Name: GRBXM 6

Total Acres: 4.20 Usable Acres: 4.20
FSA Number: 1
Tract: 462
Location: Greene
Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft
Distance to stream: 0 ft

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2014	5.7	H(69 P ppm)	M(76 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
5	EnC3	Elioak
84	Hb	Hatboro
11	MvB	Meadowville

Field Warnings:

Environmentally Sensitive Soils due to:

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

Field Name: GRBXM 7

Total Acres: 13.70 Usable Acres: 13.70

FSA Number: 8

Tract: 462

Location: Greene

Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Su-2015	7.2	L+(20 P ppm)	M(72 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
3	DkC3	Dyke
5	EnC3	Elioak
54	Hb	Hatboro
38	MvB	Meadowville

Field Warnings:

Environmentally Sensitive Soils due to:

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

Field Name: GRBXM 9

Total Acres: 5.30 Usable Acres: 5.30

FSA Number: 16

Tract: 462

Location: Greene

Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K	Lab
	[NO TEST]			

Soils:

PERCENT	SYMBOL	SOIL SERIES
2	AsC	Ashe
3	AsD	Ashe
95	Hb	Hatboro

Field Warnings:

Environmentally Sensitive Soils due to:

Soils with potential for leaching based on soil texture or excessive drainage

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

Soils with perent slope in excess of 15%

Field Name: GRBXM 10

Total Acres: 20.40 Usable Acres: 20.40

FSA Number: 8

Tract: 462

Location: Greene

Slope Class: C Hydrologic Group: C

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2017	5.8	H-(58 P ppm)	M-(70 K ppm)	A&L Mill	

Soils:

PERCENT	SYMBOL	SOIL SERIES
5	AsC	Ashe
4	CgB	Chatuge
23	DkC3	Dyke
24	EnC3	Elioak
9	Hb	Hatboro
35	MvB	Meadowville

Field Warnings:**Tract Name:** 464

FSA Number: 464

Location: Greene

Field Name: GRBXM 5

Total Acres: 18.20 Usable Acres: 18.20

FSA Number: 11, 13

Tract: 464

Location: Greene

Slope Class: C Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2017	5.9	M+(46 P ppm)	VH(295 K ppm)	A&L MIII	

Soils:

PERCENT	SYMBOL	SOIL SERIES
23	AsD	Ashe
1	EIB	Elioak
29	EnC3	Elioak
38	Hb	Hatboro
9	MvB	Meadowville

Field Warnings:

Environmentally Sensitive Soils due to:

Soils with potential for leaching based on soil texture or excessive drainage

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

Soils with perent slope in excess of 15%

Field Name: GRBXM 8

Total Acres: 17.10 Usable Acres: 17.10

FSA Number: 14, 15

Tract: 464

Location: Greene

Slope Class: B Hydrologic Group: D

Riparian buffer width: 0 ft

Distance to stream: 0 ft

Conservation Practices:

Pasture (>75% cover)

P-Index Summary

N-based

Phosphorus Limit method: Phosphorus Environmental Threshold (PET) method

Soil Test Results:

DATE	PH	P	K		Lab
Fa-2017	6.1	H-(58 P ppm)	VH(365 K ppm)	A&L Mill	

Soils:

PERCENT	SYMBOL	SOIL SERIES
2	DkB3	Dyke
17	DkC3	Dyke
15	EnC3	Elioak
51	Hb	Hatboro
15	MvB	Meadowville

Field Warnings:


Environmentally Sensitive Soils due to:

Soils with high potential for subsurface lateral flow based on soil texture and poor drainage

MAPS

Recyc SystemsTM Inc.

(Biosolids Land Application)



Scale: 1" = 2 miles

GRBXM 1-10


5-21-18

VICINITY MAP



Recyc SystemsTM Inc.

(Biosolids Land Application)




Scale: 1" = 1 mile

GRBXM 1-10

5-21-18

VICINITY MAP






5-21-18

Vicinity Map

1 in = 2 miles






5-21-18

Vicinity Map


1 in = 1 miles



5-21-18

Tax Map

1 in = 660 feet



5-21-18

Tax Map

1 in = 660 feet




ADJOINING LANDOWNERS

Bobby McDaniel

GREENE COUNTY

Tax Map	Parcel #	Owner Name(s)
38-A	113	Richard L. and Marie C. Durrer
	121	James A. Loder and Jennifer M. Paulson
	130	Richard R. and Eleanor J. Harris
	131	Church-First Bible Baptist
		Travenor and Evelyn Harlow Trustees, Harlow Revocable Living
	132	Trust
	133	Tina Marie Harlow c/o Tina Boger
		Travenor and Evelyn Harlow Trustees, Harlow Revocable Living
38-8	1	Trust
38-9	1	Evelyn P. Deane
	2	Evelyn P. Deane
38-10	3	Lenis D. and Craig Gibson
	3A	Lenis D. and Craig Gibson
	4A1	Ginger McDaniel and Billy Jo Fitzgerald
	4A2	Bobby F. and Joann C. McDaniel
	4B2	Bobby F. and Joann C. McDaniel
50-A	3	Rapidan Service Authority
50-32	1	Milton Oliver
	C	Mundies LLC
	D	Mickey Winky and Speedy's LLC c/o Boyd McCauley
	D1	Elite Custom Ironworks LLC
	E	TWP Properties LLC
	H	Chris Anderson
50-33	C	Rapidan Service Authority

Tax Map	Parcel #	Owner Name(s)
51-A	1	Barbara B. and W. Jesse III Nimmo
	2	Barbara B. Nimo
	3A	Bradley T. and Jennifer McDaniel
	4	Josiah Hundley
	9A	Marshall L. and Violet H. Watson
51-4	5	Stephen R. and Sandra E. Barber
	6	Michael John Harrison and Tara Yancey
51-5	1	William K. and Stephanie E. Dowell
	2	Lonny C. Tilley
	3	Gary S. Liles and Judith A. Levine
	4	Karen J. Davis





Frequently
Flooded

5-21-18

Soil Map

1 in = 660 feet




 Frequently Flooded 5-21-18

Soil Map

1 in = 660 feet





Frequently 5-21-18
Flooded

Soil Map

1 in = 660 feet





Field Id	Gross Acres
GRBXM 1	13.0
GRBXM 2	18.4
GRBXM 3	18.2
GRBXM 4	10.7
GRBXM 5	16.4
GRBXM 6	4.7
GRBXM 7	11.4
GRBXM 8	20.9
GRBXM 9	4.7
GRBXM 10	17.8
TOTAL	136.2

5-21-18

Aerial Map

1 in = 660 feet



5-21-18

Aerial Map

1 in = 660 feet



5-21-18


Aerial Map

1 in = 660 feet



1 inch = 688 feet

Farm: 659
Tract: 462



Disclaimer: Wetland identifiers do not represent the size, shape or specific determination of the area. Refer to your original dermination (CPA-026 and attached maps) for exact wetland boundaries and determinations, or contact NRCS.

USDA FSA
Greene, VA

March 30, 2016



UNITED STATES DEPARTMENT OF
AGRICULTURE



FSN 659 Tract 464
Bobby McDaniel




Disclaimer: Wetland identifiers do not represent the size, shape or specific determination of the area. Refer to your original determination (CPA-026 and attached maps) for exact wetland boundaries and determinations, or contact NRCS.

Legend For Site Plan

Symbol	Feature	Minimum Setback
	House and Well	200 feet from occupied dwelling * 100 feet from water supply wells or springs
 	Well or Spring	100 feet from water supply wells or springs
	Streams or Surface Water	35 feet with 35 foot vegetated buffer 100 feet without vegetated buffer
	Wet Spot	
	Trees and Woods	
	Private Drive	
	Rock Area/Rock Outcrop	25 feet from rock outcrops 50 feet from limestone rock outcrops
	Severely Eroded Spot	18 Inch minimum depth of soil
  	Sink Hole	100 feet from open sinkholes 50 feet from closed sinkholes
	State Road	10 feet from side of roadway
	Fence / Field Boundary	
	Property Line	100 feet from property line *
 	Slope	15% maximum
	Hashed out Area	No application

*Buffer can be reduced or waived upon written consent from landowner.




Public Access: 200 ft.
From Property line,
400 ft. from building.

5-21-18

Site Map

1 in = 660 feet






5-21-18

Site Map

1 in = 660 feet






5-21-18

Site Map

1 in = 660 feet



5-21-18

Topographic Map

1 in = 2,000 feet